

October 22, 2021

Tuolumne Utilities District

**NOTICE TO PLANHOLDERS**  
**ADDENDUM NO.1**

PROJECT: FY22 CIPP Sewer Rehabilitation Project  
TO: All Planholders  
FROM: Tuolumne Utilities District  
PROPOSAL DATE: **Thursday, October 28, 2021 @ 2:00 p.m. local time**

Notice is hereby given to prospective bidders that the Contract Documents for the FY22 CIPP Sewer Rehabilitation Project have been modified as hereinafter set forth. This Addendum No.1 shall form a part of the Contract Documents and takes precedence over the original Contract Documents.

The following revisions, additions, replacements, clarifications, and/or deletions shall be made to the Contract Documents:

**REVISION: Bid Schedule**

Please replace the Bid Schedule with the attached Bid Schedule.

**REVISION: Summary of Work**

Please replace page one of Section 01010-Summary of Work and Contract Considerations with the attached page one of Section 01010.

- Revised Section 1.01.a.1
- Removed reference to 18" CIPP from Section 1.01.b
- Revised Section 1.01.b referencing measurement for payment for Service Reinstatements

**REVISION: Exhibit "A"- Summary of Scope of Work**

Please replace Exhibit "A" with the attached Exhibit "A". Segments 13 and 14 were removed from the Scope of Work.

Bidders shall acknowledge receipt of Addendum No.1 in the space below and include this page with the bid. Failure to do so may subject bidder to disqualification.



\_\_\_\_\_  
Erik D. Johnson, P.E.  
District Engineer

I acknowledge receipt of Addendum No.1, consisting of four (4) pages, including this page.

Company Name: \_\_\_\_\_

Authorized Signature: \_\_\_\_\_

**FY22 CIPP Sewer Rehabilitation  
Project**

**BID SCHEDULE**

(revised 10/22/2021, Addendum No.1)

***All Bid Schedules must be completed***

<b>Item No.</b>	<b>Item</b>	<b>Units</b>	<b>Estimated Quantity</b>	<b>Unit Price</b>	<b>Total Estimated Price</b>
1.	Mobilization & Demobilization	LS	1		
2.	12" Diameter CIPP	LF	281		
3.	14" Diameter CIPP	LF	1,110		
4.	15" Diameter CIPP	LF	702		
5.	16" Diameter CIPP	LF	1,582		
				<b>TOTAL</b>	

**TOTAL BASE BID PRICE**

TOTAL LUMP SUM BID PRICE

\$ \_\_\_\_\_ (figures)

Owner expects, but is not required, to award the contract to the lowest responsive responsible Bidder upon the basis of the lowest total bid price of the lump sum unless all or some of the bids are rejected.

The undersigned Bidder acknowledges receipt of the following Addenda, which have been considered in preparation of this Bid:

No.: \_\_\_\_\_ Dated: \_\_\_\_\_

No.: \_\_\_\_\_ Dated: \_\_\_\_\_

No.: \_\_\_\_\_ Dated: \_\_\_\_\_

Dated in \_\_\_\_\_ this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_.

## **SECTION 01010**

### **SUMMARY OF WORK AND CONTRACT CONSIDERATIONS**

#### **1.01 WORK COVERED BY CONTRACT DOCUMENTS**

- a. The Work covered by these Contract Documents consists generally of providing the following:
  - 1. Furnish and install Cured-In-Place Pipe at various locations ranging from 12" to 16" including pre and post installed CCTV and reinstatement of laterals, as appropriate.
  
- b. Each item in the Bid Schedule is described below:

Each item is installed per standard TUD specifications.

- 1. Mobilization and Demobilization (Lump Sum): Not to exceed five percent (5%) of the total of all Unit Prices. All precleaning and video inspection prior to lining shall be paid for in the unit prices for the pipe segments.
- 2. 12" Diameter CIPP (Lineal Foot): Furnish and install 12" Cured-In-Place Pipe. Measurement for payment shall be actual footage installed.
- 3. 14" Diameter CIPP (Lineal Foot): Furnish and install 14" Cured-In-Place Pipe. Measurement for payment shall be actual footage installed.
- 4. 15" Diameter CIPP (Lineal Foot): Furnish and install 15" Cured-In-Place Pipe. Measurement for payment shall be actual footage installed.
- 5. 16" Diameter CIPP (Lineal Foot): Furnish and install 16" Cured-In-Place Pipe. Measurement for payment shall be actual footage installed.
- 6. Service Reinstatements – NOT INCLUDED IN BID SCHEDULE- (Each) Furnish and perform reinstatements at connections along the lined pipe. Measurement for payment shall be on a time and material basis per the Contract Documents.

#### **1.02 TYPE OF CONTRACT**

- a. The Work covered by these Contract Documents shall be provided under a single Contract.
  
- b. All bid items shall be paid based on the measured quantities. The quantities in the Bid Schedule are estimates for the purposes of bidding.

**EXHIBIT "A" - SUMMARY OF SCOPE OF WORK**

Segment No.	Lining Segment	Día/Matl	Upstream Depth (Rim to Invert)	Downstream Depth (Rim to Invert)	Trutape Length from Rim to Rim (lf)	Svc Reinstatements	Drivable Access to Upstream SMH?	Drivable Access to Downstream SMH?	Notes
1	1419-1418, SOUTHGATE DR	14"/ACP	4'2"	4'7"	31'	0	YES	YES	
2	1418-1417, SOUTHGATE DR	14"/ACP	4'7"	5'3"	328'	0	YES	YES	
3	1417-1416, SOUTHGATE DR	14"/ACP	5'3"	7'1"	145'	0	YES	YES	
4	1416-1415, SOUTHGATE DR	14"/ACP	7'1"	7'6"	189'	0	YES	YES	
5	1413-1412, SOUTHGATE DR	15"/ACP	6'4"	5'4"	311'	0	YES	YES	
6	1412-1411, SOUTHGATE DR	12"/ACP	5'4"	3'8"	281'	0	YES	YES	
7	1411-1410, SOUTHGATE DR	14"/ACP	3'8"	4'7"	417'	0	YES	YES	
8	1410-1408, SOUTHGATE DR	16"/ACP	4'7"	4'6"	466'	0	YES	YES	
9	1408-1407, SOUTHGATE DR	16"/ACP	4'6"	5'3"	501'	0	YES	YES	
10	1407-1406, SOUTHGATE DR	16"/ACP	5'3"	5'5"	300'	0	YES	YES	
11	1406-1405, SOUTHGATE DR	16"/ACP	5'5"	5'6"	315'	0	YES	YES	
12	1401A-896, SOUTHGATE DR	15"/ACP	5'2"	6'0"	391'	0	YES	NO	
<del>13</del>	<del>896-895, SOUTHGATE DR</del>	<del>18"/ACP</del>	<del>6'0"</del>	<del>5'11"</del>	<del>100'</del>	<del>0</del>	<del>NO</del>	<del>YES</del>	
<del>14</del>	<del>895-894, SOUTHGATE DR</del>	<del>18"/ACP</del>	<del>5'11"</del>	<del>4'3"</del>	<del>400'</del>	<del>0</del>	<del>YES</del>	<del>YES</del>	

**Totals**      3,675'      **lf**

12-inch	281 lf
14-inch	1110 lf
15-inch	702 lf
16-inch	1582 lf
<del>18-inch</del>	<del>500 lf</del>